

SERVICE



BULLETIN



PLEASE NOTE
THE SERVICE
DEPT FAX
NUMBER
01536 721110

TO: All Versalift Users

SUBJECT: Flyboom pivot bearings

SERVICE BULLETIN REF. 05/0502

DATE: April 05

On a number of recent occasions it has been found that the bolts securing the bearing housings on the top and bottom flyboom pivots have been allowed to remain loose for a considerable period of time. We must point out that these considered to be a critical fastener and are marked with sentry seal on production. This therefore requires these bolts to be part of the operators daily inspection and a careful check during all routine services to ensure that they are retightened if they should become loose.

Failure to ensure that these securing bolts are tight could lead to fretting between the bearing housing and the flyboom structure as well as elongation of the bolt holes.

This bulletin is for technical information purposes only and does not constitute authority for mandatory replacement of parts or warranty claim submission.

If you have any questions, or if further information is required, please contact the Versalift Technical Help Line on 01536 721010

Versalift Distributors (UK) Ltd 1 Altendiez Way Latimer Park Burton Latimer Northants. NN15 5YZ
Tel. 01536 721010 Fax 01536 721110 Email: admin@versalift.co.uk